



NOTES:

1. EXACT LOCATIONS OF LOCKBOXES TO BE DETERMINED BY UCSC FIRE AND POLICE DEPARTMENTS. PROVIDE DUAL LOCK BOX PEDESTALS AT ALL MAJOR ROADS.
2. ALTERNATE LOCATIONS FOR LOCKBOXES BY BUILDING ENTRIES TO BE DETERMINED BY UCSC POLICE AND/OR FIRE DEPARTMENTS.
3. CONCRETE TO BE 3000 PSI MIN., PROVIDE SACK FINISH. ALL WORK TO CONFORM TO UBC AND ACI STANDARDS.
4. UNIVERSITY TO PROVIDE LOCKBOXES AND CONCRETE MOUNTING KIT.
5. CAULK AROUND LOCKBOX WITH CLEAR SILICONE CAULK AS NECESSARY TO SEAL WATERTIGHT.
6. WHERE POLICE AND FIRE AGREE ON LOCATION, CONSIDER PLACING 2 BOXES IN ONE PEDESTAL.

UNIVERSITY OF CALIFORNIA SANTA CRUZ Physical Planning and Construction	SHEET TITLE	DRAWN	LOCATION	FILE NO.
	LOCKBOX	OAC		REF
	BUILDING OR PROJECT	CHECKED	SCALE	SHEET
	CAMPUS STANDARDS	PP&C	1"=40.0'	11.2-01
		APPROVED	DATE	OF
			02/05/02	