



Rating form completed by:

RUTHERFORD + CHEKENE ruthchek.com Evaluator: JY/WAL/BL Date: 06/28/2019

ROFESSIO

Exp. 12-31-20

3950

06-28-19


Text in green is to be part of UC Santa Cruz building database and may be part of UCOP database

DATE: 2019-06-28

UC Santa Cruz building seismic ratings Visual Arts Facilities-Building H


CAAN #7784

427 Baskin Arts Service Road, Santa Cruz, CA 95064 UCSC Campus: Main Campus





Plan



Rating summary	Entry	Notes
UC Seismic Performance Level (rating)	IV (Fair)	
Rating basis	Tier 1	ASCE 41-17 ¹
Date of rating	2019	
Recommended UC Santa Cruz	В	Priority A=Retrofit ASAP
priority category for retrofit	U	Priority B=Retrofit at next permit application
Ballpark total construction cost to retrofit to IV rating ²	None	See recommendations on further evaluation and retrofit.
Is 2018-2019 rating required by UCOP?	Yes	Building was not previously rated.
Further evaluation recommended?	Yes	Investigation Line C roof-to-wall connections at the time of re-roofing and possible improvement for north-south out-of-plane loading

¹ We translate this Tier 1 evaluation to a Seismic Performance Level rating using professional judgment. Non-compliant items in the Tier 1 evaluation do not automatically put a building into a particular rating category, but we evaluate such items along with the combination of building features and potential deficiencies, focused on the potential for collapse or serious damage to the gravity supporting structure that may threaten occupant safety. See Section III.B of the 19 May 2017 *UC Seismic Safety Policy* and Method B of Section 321 of the 2016 *California Building Code*.

² Per Section III.A.4.i of the 26 March 2019 *UC Seismic Program Guidebook, Version 1.3*, the cost includes all construction cost necessitated by the seismic retrofit, including restoration of finishes and any triggered work on utilities or accessibility. It does not include soft costs such as design fees or campus costs. The cost is in 2019 dollars.

Building information used in this evaluation

- Architectural drawings by Gary Garmann Architects, "UCSC BASKIN VISUAL ARTS Plaster Studio and Facility Office Additions," revisions dated 1 May 1989, stamped by State Fire Marshal on 8 February 1990, Sheets A1-A6.
- Structural drawings by Donald C. Urfer & Associates, Inc., "UCSC BASKIN VISUAL ARTS Plaster Studio and Facility Office Additions," revisions dated 10 October 1989, Sheets S1-S3. S4 and S5 are plans for alternate foundation plans. For the purpose of this evaluation, we assume the building is built per the foundations shown on Sheets S1-S3.

Additional building information known to exist

None

Scope for completing this form

Reviewed structural drawings, made brief site on 23 May 2019, and carried out ASCE 41-17 Tier 1 evaluation.

Brief description of structure

Baskin Building H is a two-story building at the northeast region of the Department of Art's Baskin Visual Art studios complex. It houses approximately 3,000 square foot of program space, with 1,200 square feet of office area in the lower level and a 1,780 square feet plaster studio at the main level. The metal studio (Building P CAAN#7929) is to the west, and Building B (CAAN #7494) is to the south. A retaining wall supports the east edge of the north courtyard of the complex and runs south from Building H to Building B. The out-to-out dimensions for the rectangle are 44'-0" in the north-south direction and 40'-6" in the east-west direction. The building is on a sloped site which is low to the north and east side which corresponds to the lower level elevation and high on the south and west side which corresponds to the lower level elevation as the north courtyard. The elevation of the high edge and the valley of the roof are at 21'-6" and 9'-0" respectively above the main level floor elevation. The lower level floor is at 10'-0" below the main level. Architecturally, at the main level, Building H has two lines of steel truss frames and one line of wood frame wall in the longitudinal direction (E-W direction) and regular wood frame stud wall in the transverse direction (N-S direction). The lower level has concrete retaining walls on the upslope sides and wood walls at the downslope side. The building was designed in 1989 by architect Gary Garmann Architects, and the structural engineer was Donald C. Urfer & Associates, Inc.

The roof is comprised of plywood over wood joists that span north-south between east-west steel trusses at the north and center and a wood stud wall at the south façade. The main floor system has plywood over wood joists that spans between glulam beams which are in turn supported by wood posts at 8' apart E-W and 11' apart N-S. Truss posts from above terminate at the main floor level and are supported either by concrete foundation walls where occurs along the perimeter or by 6x6 wood posts at the interior.

<u>Identification of levels</u>: The building site slopes to the northeast. The building is comprised of two levels above the lowest perimeter grade: a partial basement (lower level) on the east side and a full main level at the same elevation of the north courtyard.

<u>Foundation system</u>: The west perimeter wall bears on a 6" concrete curb on the west and south. The 6" concrete curbs are reinforced with #4 bars at 12" o.c. each way above grade. Below grade, the curb thickens to a 12" concrete wall to support the continuous 2x6 flat plate on top of which the 2x12 floor joists bear. The 12" concrete wall is reinforced with two layers of #4 bars at 16" o.c. each way. Where the glulam floor beams occur, a 16" wide by 20" pilaster, reinforced with four #5 bars and four #3 ties, is provided. The 12" concrete wall is in turn supported by a 1'-6" deep by 3'-0" wide continuous strip footing that is reinforced with three #5 bars top and bottom and then with #4 bars spaced at 9" on center. (See Detail 4/S3 for the concrete curb and wall connection on the west elevation.) Concrete piers, 24" or 36" diameter by 8'-0" minimum long, are provided to support the strip footings at 11'-0" on center. The concrete piers are typically reinforced with two #5 vertical bars on the downhill side (east side) and three #5 bars on the uphill side (west side) with #3 stirrups spaced at 12" o.c.

The east perimeter wall bears directly on top of an 18"x18" concrete strip footing reinforced with two #5 bars top and bottom with #3 ties at 24" o.c. per Detail 1/S3.

The north perimeter wall of the crawl space starts with a 6'-0" long concrete curb over strip footing level with the higher grade level, with the same dimension and reinforcement as the west perimeter foundation and with 24" diameter concrete piers below each end. Then the strip footing changes to an approximately 12'-6" long concrete grade beam that steps to follow the finish grade slope. These grade beams are 12" wide by 24" deep with three #5 bars top and bottom with possibly #3 stirrups at 16" o.c. As shown on foundation plan on Sheet S2 and per Detail 14/S3, the grade beam is supported by two 36" diameter concrete piers at 8'-0" from the grade beam ends and between. Then as grade flattens at the lower level, the wood wall bears directly on top of the basement slab at the lower grade level, same as the east perimeter wall per Detail 1/S3.

The south perimeter wall bears on a concrete curb over strip footing, same as the west wall, for approximately 20'-6" long from west end of the building to the end of the retaining wall location. The concrete strip footings are supported with three concrete piers at 8'-0" o.c. Then beyond the retaining wall, the exterior wood wall extends below main level and bears directly on a 1'6" by 1'6" strip footing at the lower grade level, same as the east perimeter wall per Detail 1/S3.

The interior retaining wall is the separation between the west crawl space and the east lower level and was extended continuously from Building B to support the elevated north courtyard. There does not appear to be a joint where the north-south exterior courtyard retaining wall meets the east-west building retaining wall. The 8" concrete retaining walls are typically reinforced with #4 bars at 16" o.c. each way and supported by a continuous 1'-6" deep by 2'-0" wide strip footing which is reinforced with two #5 bars top and bottom tied together with #3 stirrups at 24" o.c. (See Detail 6/S3 for this connection detail.) The basement slab is 6" thick with #5 bars at 10" o.c. in the N-S direction and #4 at 18" o.c. in the E-W direction. The slab is thickened around the perimeter when connecting into the perimeter footings.

The interior 6x6 wood posts are anchored into a 1'-6" diameter round concrete curb on top of the typical 24" diameter concrete piers with 6" above basement floor per Detail 7/S3.

Structural system for vertical (gravity) load: The roof bears on 2x12 joists spaced @ 16" o.c. spanning in the N-S direction to the steel trusses or wood bearing walls. At the roof valley, roof joints are supported by the lower horizontal truss chord by bearing onto a steel plate welded to the side of the tube per Detail 10/A5. At roof high points on Gridlines A and B, roof joists are supported by an upper horizontal chord by bearing directly on it per Detail 7/A5. At the south perimeter, the roof joists bearing on the top double plate over the wood bearing wall per Detail 4/A5. The trusses are typically comprised of structural steel tubes welded directly together without gusset plates. The trusses are supported by steel tube posts, and the posts bear on the concrete foundation (or into the 6x6 posts and the interior and into the foundation on the northeast location).

The main level floor is supported by 2x12 Douglas Fir #2 floor joists spaced at 16" o.c. spanning in the N-S direction to glulam floor beams. The glulam beams are typically single span 5 1/8" wide by 10 ½" deep members spanning between 6x6 wood posts and pilasters in the west perimeter concrete wall. 6x6 posts are spaced at 8'-0" E-W direction and 11'-0" N-S direction. The material type and grade of the glulam beams and the 6x6 posts are unknown due to the unavailability of the specifications. Typical perimeter walls are comprised of 2x6s spaced at 16" o.c. with $\frac{3}{4}$ " plywood wall sheathing.

<u>Structural system for lateral forces:</u> In the N-S direction, the lateral forces at the roof are delivered from the $\frac{1}{2}$ " plywood roof diaphragm at each sloped sawtooth roof panel to the east and west plywood walls. The trusses span vertically for out-of-plane loads between the top and bottom of the roof panels. At the valley, per Detail 10/A5, north-south out-of-plane loads are resisted by a $\frac{1}{2}$ " x 3" steel plate welded to the vertical chord of the truss at 8'-0" o.c. and then bolted to the roof framing with $\frac{1}{2}$ " diameter bolts. At the two high roof eaves, per Detail 7/A5, north-south out-of-plane loads are resisted with an unusual detail with 2x6s nailed to the roof joists capturing the steel top chord in bearing, together likely with toe nails from the joists to a 2x6 top plate with welded studs to the steel top chord tube. At the roof low eave, per Detail 4/A5, north-south out-of-plane loads appear to likely only have toe nails from the joists to the wall top plate and partial resistance from the blocking, nailing and clips detailed for inplane loads. At the north wall, per Detail 10/A5, north-south out-of-plane loads are transferred at the top of the wood wall to the bottom chord of the truss with a 4"x6-1/4" continuous nailer and 5/8" threaded welded studs at

32" o.c. The steel truss posts that continue down to the main floor are also bolted to the wood studs in the wall per Detail 13/S3.

North-south forces at the main level are delivered to the main level plywood floor diaphragm and then to the west retaining wall and east lower level stud wall and down to the foundation. Per Detail 2/S2, in-plane loads are transferred from the floor to the top of the lower story wall top plate through blocking and then nailing into a sill plate which is bolted to the top of the concrete. Out-of-plane straps are also provided from the top plate to blocking.

In the E-W direction, lateral loads in the roof diaphragm are delivered through the diaphragm to south and north plywood shear walls. Because of the sawtooth nature of the diaphragm, it is made up of the two sloped plywood panels and the vertical trusses on Lines B and C, and internal forces within the diaphragm must pass from the plywood portions through the truss members. In-plane east-west loads at the low roof eave at Line C, per Detail 4/A5, are transferred from blocking through L50 clips at each joist bay into the top plate. At Line B, east-west internal diaphragm shear loads are transferred per Detail 10/A5 at the low eave from blocking to L50 clips to a 2x6 nailer through threaded welded studs to a ½" plate welded to the truss bottom chord. At the high eave on Lines A and B, per Detail 7/A5, east-west internal diaphragm shear loads are transferred from blocking to the top of the truss top chord.

East-west loads at the main level are delivered to the main level plywood floor diaphragm and then to the north and south stepped retaining walls/wood stud walls and down to the foundation.

The typical exterior truss posts are anchored atop of the concrete curb with two 5/8" anchor bolts as per Detail 9/S3. The two interior truss posts at the north elevation and the exterior one at the east elevation are welded to a builtup ' Π ' shape steel bracket with two ½" through bolts to the glulam floor beam, which in turn are anchored into the concrete curb below per Detail 8/S3. The truss post on the northeast corner is welded to a ½" thick plate anchored with two 5/8" anchor rods each side through the continuous double top plate atop 6x6 wood post in the wood frame wall per Detail 2/S3.

<u>Building condition</u>: During the site visit, the lower level was not observed. All exposed structural steel frame and connections appeared to be in relatively good condition. No stains from water leaks were seen inside the studio.

<u>Building code</u>: The building code used for design is not listed on the architectural or structural drawings. The earliest date on the drawings is 21 December 1988. A 2016 history of building codes in California is provided in "Abridged History of San Francisco's Bureau of Building Inspection: 1944 to 1992," by Lonnie Haughton of Richard Avelar & Associates and informs the following. In 1978, the State Building Standards Commission was given responsibility for state building codes. The 1985 State Building Code adopted the 1982 Uniform Building Code (UBC), with an effective date of 1 October 1985. In 1989, the first California Building Code was developed; it adopted the 1988 UBC, with an effective date of 1 July 1989 for State projects. Building Code/California Building Codes were used. It thus appears likely that the 1988 UBC was the building code used for Building H.

Brief description of seismic deficiencies and expected seismic performance including mechanism of nonlinear response and structural behavior modes

Potential seismic deficiencies of the building include the following:

For east-west loads, the sawtooth configuration at the roof creates a type of vertical irregularity. It also combines sloped plywood panels and steel trusses and requires loads to pass through a fairly complicated set of details to span from shear walls at Line C to the shear wall below the truss and clerestory window on Line A. As the diaphragm deforms, there is no horizontal tie or chord at the bottom chord level in the west and east walls, so the diaphragm will have a tendency to unfold and deform farther than it would if were a single plane. The connection of the roof framing to the lower chord of the truss at roof valley may induce out-of-plane forces and torsion to the truss. The roof diaphragm also lacks cross ties except for the central truss.

• For north-south loads, out-of-plane transfer of loads from the top of the wall on Line C into the roof joists likely relies only on toe nails with limited capacity, but the joists run over the top plate.

Inelastic behavior will likely be distributed in the roof diaphragm and the wall and possibly at the Line C roof-to-wall connection. There could also be movement due to differential settlement and slope stability from the unbalanced load of the hillside site. Evaluation of slope stability is beyond the scope of the Tier 1 evaluation.

Structural deficiency	Affects rating?	Structural deficiency	Affects rating?
Lateral system stress check (wall shear, column shear or flexure, or brace axial as applicable)	N	Openings at shear walls (concrete or masonry)	N
Load path	Y	Liquefaction	Ν
Adjacent buildings	N	Slope failure	N
Weak story	N	Surface fault rupture	N
Soft story	N	Masonry or concrete wall anchorage at flexible diaphragm	N
Geometry (vertical irregularities)	Y	URM wall height-to-thickness ratio	N
Torsion	N	URM parapets or cornices	N
Mass – vertical irregularity	N	URM chimney	N
Cripple walls	N	Heavy partitions braced by ceilings	N
Wood sills (bolting)	Ν	Appendages	Ν
Diaphragm continuity	N		

Summary of review of nonstructural life-safety concerns, including at exit routes.³

No apparent falling hazard items were observed in the studio during our brief visit. Basement rooms were not observed during the site visit and are therefore excluded from the scope of the nonstructural review. It is not known if they contain any natural gas-fueled equipment.

UCOP nonstructural checklist item	Life safety hazard?	UCOP nonstructural checklist item	Life safety hazard?
Heavy ceilings, feature or ornamentation above large lecture halls, auditoriums, lobbies or other areas where large numbers of people congregate	None observed	Unrestrained hazardous materials storage	None observed
Heavy masonry or stone veneer above exit ways and public access areas	None observed	Masonry chimneys	None observed
Unbraced masonry parapets, cornices or other ornamentation above exit ways and public access areas	None observed	Unrestrained natural gas-fueled equipment such as water heaters, boilers, emergency generators, etc.	Unknown

Basis of rating

The building is assigned as a Seismic Performance Level rating of Level IV. Demands in the plywood shear walls are low. Although the sawtooth roof combination of plywood panels and steel trusses is unusual and will have increased flexibility due to a lack of a horizontal tie, the spans are relatively short, and loads in the trusses and plywood are relatively low. The building is generally well tied together, though there are various eccentricities in the load path. At the Line C roof-to-wall connection, there appears to be limited capacity, but the rafters span over the top of the wall, so loss of vertical support is unlikely. Slope stability considerations have not been considered in the rating.

³ For these Tier 1 evaluations, we do not visit all spaces of the building; we rely on campus staff to report to us their understanding of if and where non-structural hazards may occur.

Recommendations for further evaluation or retrofit

When the building is re-roofed, we recommend investigation of the Line C roof-to-wall connection and possible improvement for north-south out-of-plane loading if only toe nails are found between the joists and top plate.

Peer review of rating

This seismic evaluation was discussed in a peer review meeting on 24 June 2019. Reviewers present were Joe Maffei of Maffei Structural Engineering and Jay Yin of Degenkolb Engineers. Comments from the reviewers have been incorporated into this report. The reviewers agreed with the assigned rating.


Additional building data	Entry	Notes
Latitude	36.995080	
Longitude	-122.061000	
Are there other structures besides this one under the same CAAN#	No	
Number of stories above lowest perimeter grade	2	The building is below grade on the west side more than ½ level
Number of stories (basements) below lowest perimeter grade	0	
Building occupiable area (OGSF)	3,074	From UCSC facilities database.
Risk Category per 2016 CBC Table 1604.5	П	
Estimated fundamental period	0.14 sec	Estimated using ASCE 41-17 equation 4-4 and 7-18
Building structural height, h _n	25 ft	Structural height defined per ASCE 7-16 Section 11.2
Coefficient for period, Ct	0.020	Estimated using ASCE 41-17 equation 4-4 and 7-18
Coefficient for period, eta	0.75	Estimated using ASCE 41-17 equation 4-4 and 7-18
Site data		
975-year hazard parameters S_s , S_1	1.281, 0.485	From SEAOC/OSHPD website
Site class	D	
Site class basis	Geotech ^₄	See footnote below
Site parameters F_a , F_v	1.0, 1.815	From SEAOC/OSHPD website
Ground motion parameters S_{cs} , S_{c1}	1.281, 0.881	From SEAOC/OSHPD website
S_{α} at building period	1.28	
Site V _{s30}	900 ft/s	


⁴ Determination of site class and assessment of geotechnical hazards are based on correspondence with Pacific Crest Geotechnical Engineers and Nolan, Zinn, and Associates Geologists. [*Revised Geology and Geologic Hazards, Santa Cruz Campus, University of California*, Job # 04003-SC 13 May 2005]. Site class is taken as D throughout the main campus of UC Santa Cruz. The following links provide hazard maps for liquefaction, landslide, and fault rupture:

https://gis.santacruzcounty.us/mapgallery/Emergency%20Management/Hazard%20Mitigation/LiquifactionMap2009.pdf https://gis.santacruzcounty.us/mapgallery/Emergency%20Management/Hazard%20Mitigation/LandslideMap2009.pdf https://gis.santacruzcounty.us/mapgallery/Emergency%20Management/Hazard%20Mitigation/FaultZoneMap2009.pdf

V _{s30} basis	Estimated	Estimated based on site classification of D.
Liquefaction potential	Low	
Liquefaction assessment basis	County map	See footnote below
Landslide potential	Low	
Landslide assessment basis	County map	See footnote below
Active fault rupture identified at site	No	
Fault rupture assessment basis	County map	See footnote below
Site-specific ground motion study?	No	
Applicable code		
Applicable code or approx. date of original construction	Original Built: 1990 (Estimated) Code: 1988 UBC	
Applicable code for partial retrofit	None	No partial retrofit.
Applicable code for full retrofit	None	No full retrofit
FEMA P-154 data		
Model building type North-South	W2 -Wood Frame	
Model building type East-West	Steel Truss Frame/W2- Wood Frame	S2 checklist in ASCE 41-17 is used to check truss elements.
FEMA P-154 score	N/A	Not included here because we performed ASCE 41 Tier 1 evaluation.
Previous ratings		
Most recent rating	-	Not evaluated before.
Date of most recent rating	-	
2 nd most recent rating	-	
Date of 2 nd most recent rating	-	
3 rd most recent rating	-	
Date of 3 rd most recent rating	-	
Appendices		
ASCE 41 Tier 1 checklist included here?	Yes	Refer to attached checklist file.


Basement Level Plan






Section AA


Section BB



Truss Elevation



Connection Details on Sheet S3



APPENDIX A

Additional Photos



Southeast Corner (Looking Northwest)



North Elevation (Looking South)



Southwest Corner (Looking East)



Northwest Corner (Looking Southeast)



Steel Truss at North Exterior Wall (Grid A, Looking North)



Steel Truss at Roof Intersection (Grid B, Looking North)

APPENDIX B

ASCE 41-17 Tier 1 Checklists (Structural)

UC Campus:	Sa	Date:	06/28/2019				
Building CAAN:	7784	Auxiliary CAAN:	By Firm:	Ruth	erford + Che	kene	
Building Name:	Elena Baskin V	Initials:	JY	Checked:	WAL/BL		
Building Address:	427 Baskin Arts Service	Page:		of			
ASCE 41-17							

Collapse Prevention Basic Configuration Checklist

LOW SEISMICITY

BUILDING SYSTEMS - GENERAL

			Description
C	N/A		LOAD PATH: The structure contains a complete, well-defined load path, including structural elements and connections, that serves to transfer the inertial forces associated with the mass of all elements of the building to the foundation. (Commentary: Sec. A.2.1.1. Tier 2: Sec. 5.4.1.1)
			Comments: Roof diaphragms deliver loads to plywood shear walls over strip footings with concrete piers in the N-S direction and to steel trusses and plywood shear walls over strip footings with concrete piers in the E-W direction.
C	N/A □'	-	ADJACENT BUILDINGS: The clear distance between the building being evaluated and any adjacent building is greater than 0.25% of the height of the shorter building in low seismicity, 0.5% in moderate seismicity, and 1.5% in high seismicity. (Commentary: Sec. A.2.1.2. Tier 2: Sec. 5.4.1.2) Comments: There are no adjacent structures.
с 0	N/A		MEZZANINES: Interior mezzanine levels are braced independently from the main structure or are anchored to the seismic- force-resisting elements of the main structure. (Commentary: Sec. A.2.1.3. Tier 2: Sec. 5.4.1.3) Comments: There are no mezzanines.

BUILDING SYSTEMS - BUILDING CONFIGURATION

			Description
C	N/A	_	WEAK STORY: The sum of the shear strengths of the seismic-force-resisting system in any story in each direction is not less than 80% of the strength in the adjacent story above. (Commentary: Sec. A2.2.2. Tier 2: Sec. 5.4.2.1)
			Comments: Shear wall lengths are equal or larger at the lower story compared to the main story.
C O	N/A	-	SOFT STORY: The stiffness of the seismic-force-resisting system in any story is not less than 70% of the seismic-force- resisting system stiffness in an adjacent story above or less than 80% of the average seismic-force-resisting system stiffness of the three stories above. (Commentary: Sec. A.2.2.3. Tier 2: Sec. 5.4.2.2)
			Comments: Shear wall lengths are equal or larger at the lower story compared to the main story. The lower story height is lower than the main story height.

UC Campus:	Santa Cr	uz	Date:		06/28/2019	
Building CAAN:	7784	Auxiliary CAAN:	By Firm:	Rutherford + Chekene		
Building Name:	Building Name: Elena Baskin Visual Arts Building H				Checked:	WAL/BL
Building Address:	427 Baskin Arts Service Road	l, Santa Cruz, CA 95064	Page:		of	
Co	م ollapse Prevention	uration	Check	list		
	ERTICAL IRREGULARITIES: All vert ommentary: Sec. A.2.2.4. Tier 2: Sec omments: Steel posts support the nnected into the 6x6 wood post insic	c. 5.4.2.3) e ends of the streel trusses.	At the northea	st corner of	the building, the	
DDDD ⁱⁿ Se	EOMETRY: There are no changes in a story relative to adjacent stories, e ec. 5.4.2.4) omments: Shear wall lengths are	xcluding one-story penthous	ses and mezzai	nines. (Comi	mentary: Sec. A.2	
	ASS: There is no change in effective ezzanines need not be considered. (omments: The effective mass diff	Commentary: Sec. A.2.2.6.	Tier 2: Sec. 5.4	.2.5)		houses, and
	DRSION: The estimated distance be e building width in either plan dimens omments: A flexible diaphragm is	sion. (Commentary: Sec. A.2		•	rigidity is less th	an 20% of

MODERATE SEISMICITY (COMPLETE THE FOLLOWING ITEMS IN ADDITION TO THE ITEMS FOR LOW SEISMICITY)

GEOLOGIC SITE HAZARD

				Description
C D		N/A	U	LIQUEFACTION: Liquefaction-susceptible, saturated, loose granular soils that could jeopardize the building's seismic performance do not exist in the foundation soils at depths within 50 ft (15.2m) under the building. (Commentary: Sec. A.6.1.1. Tier 2: 5.4.3.1)
				Comments: There is no mapped liquefaction on https://gis.santacruzcounty.us/mapgallery/Emergency%20Management/Hazard%20Mitigation/LiquifactionMap2009.pdf.
С	NC	N/A	U	SLOPE FAILURE: The building site is located away from potential earthquake-induced slope failures or rockfalls so that it
0	0	0	0	is unaffected by such failures or is capable of accommodating any predicted movements without failure. (Commentary: Sec. A.6.1.2. Tier 2: 5.4.3.1)
				Comments: There are no mapped landslides on https://gis.santacruzcounty.us/mapgallery/Emergency%20Management/Hazard%20Mitigation/LandslideMap2009.pdf.

Note: C = Compliant NC = Noncompliant N/A = Not Applicable U = Unknown

UC Campus:	pus: Santa Cruz				06/28/2019		
Building CAAN:	7784	Auxiliary CAAN:		By Firm:	Ruth	erford + Che	kene
Building Name:	Building Name: Elena Baskin Visual Arts Building H				JY	Checked:	WAL/BL
Building Address:	Page:		of				

ASCE 41-17

Collapse Prevention Basic Configuration Checklist

MODERATE SEISMICITY (COMPLETE THE FOLLOWING ITEMS IN ADDITION TO THE ITEMS FOR LOW SEISMICITY)

GEOLOGIC SITE HAZARD

	N/A	-	SURFACE FAULT RUPTURE: Surface fault rupture and surface displacement at the building site are not anticipated. (Commentary: Sec. A.6.1.3. Tier 2: 5.4.3.1)
			Comments: There are no faults at the project site per https://gis.santacruzcounty.us/mapgallery/Emergency%20Management/Hazard%20Mitigation/FaultZoneMap2009.pdf.

HIGH SEISMICITY (COMPLETE THE FOLLOWING ITEMS IN ADDITION TO THE ITEMS FOR MODERATE SEISMICITY)

FOUNDATION CONFIGURATION

				Description
C O		N/A	_	OVERTURNING: The ratio of the least horizontal dimension of the seismic-force-resisting system at the foundation level to the building height (base/height) is greater than 0.6 <i>S</i> _a . (Commentary: Sec. A.6.2.1. Tier 2: Sec. 5.4.3.3) Comments:
				Building width B = 40.5', Building average height is H = 25', B/H = 1.62 Sa = 1.28g per SEAOC at BSE-2E 0.6 x Sa = 0.77 B/H > 0.6 Sa
C	NC	N/A	-	TIES BETWEEN FOUNDATION ELEMENTS: The foundation has ties adequate to resist seismic forces where footings, piles, and piers are not restrained by beams, slabs, or soils classified as Site Class A, B, or C. (Commentary: Sec. A.6.2.2. Tier 2: Sec. 5.4.3.4) Comments: Site Class D is assumed. There are no tie beams between the top of the piers as shown on the foundation plan and Detail 7/S2.

Note: C = Compliant NC = Noncompliant N/A = Not Applicable U = Unknown

	U	IC Ca	ampu	S: Santa C	ruz		Date:	06/28/2019		
	Buil	ding	CAA	N: 7784	Auxiliary CAAN:		By Firm:	Ruth	erford + Che	kene
	Buil	ding	Nam	e: Elena Baskin Visual	Arts Building	н	Initials:	JY	Checked:	WAL/BL
E	Buildiı	ng Ao	ddres	S: 427 Baskin Arts Service Road	d, Santa Cruz,	CA 95064	Page:		of	
	C	Coll	aps	se Prevention Struc	ASCE 4 tural Cl		t For Bu	uilding	Type W	2
LC	LOW AND MODERATE SEISMICITY									
SE	SEISMIC-FORCE-RESISTING SYSTEM									
						Descriptio	'n			
С	NC	N/A	U	REDUNDANCY: The number of lines	of shear walls	in each princip	bal direction is	greater than	or equal to 2. (C	commentary:
Ô	igodol	\bigcirc		Sec. A.3.2.1.1. Tier 2: Sec. 5.5.1.1)	- f - h H -		ations and there	- 1		
				Comments: There are two lines the E-W direction	of snear walls	In the N-S dire	ection and three	e lines of late	eral force-resistin	ig system in
С	NC	N/A	_	SHEAR STRESS CHECK: The shear stress in the shear walls, calculated using the Quick Check procedure of Section 4.4.3.3, is less than the following values: (Commentary: Sec. A.3.2.7.1. Tier 2: Sec. 5.5.3.1.1)						
0	0	\bigcirc	۲		•	•				
					Structural pane		1,000 lb/f	t		
					Diagonal sheat Straight sheath		700 lb/ft 100 lb/ft			
					All other condit		100 lb/ft			
				Comments: 5/8-inch structural p in N-S direction is 426 plf at the main at the main story and 613 plf at lower included.	story and 564	plf at lower sto	ry. The averag	e shear stre	ss in E-W direction	on is 210 plf
С	NC	N/A	U	STUCCO (EXTERIOR PLASTER) SH seismic-force-resisting system. (Comr					or stucco walls as	the primary
0	0	\odot	0	Comments: There is no stucco.	-		2. 000. 0.0.0.0)		
				Comments: mere is no succo.						
С	NC	N/A	U	GYPSUM WALLBOARD OR PLASTE						
Ô	igodol	\bigcirc	0	on buildings more than one story high A.3.2.7.3. Tier 2: Sec. 5.5.3.6.1)	with the except	tion of the uppe	ermost level of	a multi-story	building. (Comm	lentary: Sec.
				Comments: Gypsum wallboards or plaster walls are not used as shear walls.						
С	NC	N/A	U	NARROW WOOD SHEAR WALLS: N				greater that	n 2-to-1 are not u	sed to resist
0	igodol	\bigcirc	0	seismic forces. (Commentary: Sec. A.						
				Comments: Narrow wall panels	that exceed th	e 2V:1H ratio a	are not used to	resist seism	nic forces.	

Note: C = Compliant NC = Noncompliant N/A = Not Applicable U = Unknown

UC Campus:			ampu	S: Sai	Santa Cruz			06/28/2019		
	Buil	lding	CAA	N: 7784	Auxiliary CAAN:	By Firm:	Ruth	erford + Che	kene	
	Bui	lding	Nam	e: Elena Baskin Vi	isual Arts Building H	Initials:	JY	Checked:	WAL/BL	
E	Buildi	ng Ao	ddres	S: 427 Baskin Arts Service	Road, Santa Cruz, CA 95064	Page:		of		
	C	Coll	aps	e Prevention Str	ASCE 41-17 ructural Checkli	st For Bı	uilding	Type W	2	
C		N/A	U	WALLS CONNECTED THROUGH FLOORS: Shear walls have an interconnection between stories to and shear forces through the floor. (Commentary: Sec. A.3.2.7.5. Tier 2: Sec. 5.5.3.6.2) Comments: Per Detail 2/S2, four ¾" diameter bolts are provided to connect the bottom plate of panel to the double top plate of the lower story wall panel. Double top plate is continuous between glula tight to glulam at ends. Simpson L50s are provided at each side of the glulam to double top plates. Addi ST2115 strap is provided at 4'-0" on center and bent over the double top plates to connect the floo exterior wall diaphragm.					in story wall ms and butt , a Simpson	
C		N/A		HILLSIDE SITE: For structures that are taller on at least one side by more than one-half story because of a sloping site, all shear walls on the downhill slope have an aspect ratio less than 1-to-1. (Commentary: Sec. A.3.2.7.6. Tier 2: Sec. 5.5.3.6.3) Comments: Site slopes down to the north and east. Shear wall panels used to resist shear forces satisfy the intent of the 1-to-1 ratio limit.						
		N/A		CRIPPLE WALLS: Cripple walls below first-floor-level shear walls are braced to the foundation with wood structural panels. (Commentary: Sec. A.3.2.7.7. Tier 2: Sec. 5.5.3.6.4) Comments : Plywood wall panels are continuous below the floor level to the concrete foundation.					tural panels.	
C		N/A		OPENINGS: Walls with opening aspect ratios of not more than 1. the seismic forces. (Commentar Comments: No openings of	5-to-1 or are supported by adjace	ent construction tl .5.3.6.5)	nrough positi			
со	NNE	ЕСТ	ON	8						
					Descrip	tion				
C		N/A	U	WOOD POSTS: There is a posi 5.7.3.3) Comments: Simpson CB-66s bolted to the	tive connection of wood posts t				Tier 2: Sec.	
		N/A		WOOD SILLS: All wood sills are	bolted to the foundation. (Com	mentary: Sec. A.8	5.3.4. Tier 2:	Sec. 5.7.3.3)		
0	0	D		Comments: Wood sills are Schedule' on Sheet S-2.	bolted with 5/8" dia. anchor boll	ts on varies spaci	ng ref 'Plywo	od Vert. & Horiz.	Diaphragm	
C		N/A	U	GIRDER/COLUMN CONNECTION the girder and the column support Comments: Simpson CC5		Tier 2: Sec. 5.7.4	.1)		aps between	

UC Campus:	Santa C	ruz	Date:		06/28/2019		
Building CAAN:	7784	Auxiliary CAAN:	By Firm:	Rutherford + Chekene			
Building Name:	Building Name: Elena Baskin Visual Arts Building H				Checked:	WAL/BL	
Building Address:	427 Baskin Arts Service Roa	Page:		of			

ASCE 41-17

Collapse Prevention Structural Checklist For Building Type W2

HIGH SEISMICITY (COMPLETE THE FOLLOWING ITEMS IN ADDITION TO THE ITEMS FOR LOW AND MODERATE SEISMICITY)

CONNECTIONS

			Description
	N/A		WOOD SILL BOLTS: Sill bolts are spaced at 6 ft (1.8 m) or less with acceptable edge and end distance provided for wood and concrete. (Commentary: A.5.3.7. Tier 2: Sec. 5.7.3.3)
0	0	0	
			Comments: Per 'Plywood Vert. & Horiz. Diaphragm Schedule' on Sheet S-2, maximum spacing between the 5/8" diameter anchor bolts is 4'-0".

DIAPHRAGMS

				Description
С	NC	N/A	-	DIAPHRAGM CONTINUITY: The diaphragms are not composed of split-level floors and do not have expansion joints. (Commentary: Sec. A.4.1.1. Tier 2: Sec. 5.6.1.1)
\mathbb{C}	0	\bigcirc	igodol	
				Comments: First floor is level, no expansion in the floor and roof diaphragm.
-	NC	N/A	-	ROOF CHORD CONTINUITY: All chord elements are continuous, regardless of changes in roof elevation. (Commentary: Sec. A.4.1.3. Tier 2: Sec. 5.6.1.1)
0	O	\bigcirc	igodol	,
				Comments: Chord discontinuity occurs at roof valley.
С	NC	N/A	U	DIAPHRAGM REINFORCEMENT AT OPENINGS: There is reinforcing around all diaphragm openings larger than 50%
0		O	-	of the building width in either major plan dimension. (Commentary: Sec. A.4.1.8. Tier 2: Sec. 5.6.1.5)
				Comments: No large opening observed in the roof diaphragm.
С	NC	N/A	U	STRAIGHT SHEATHING: All straight-sheathed diaphragms have aspect ratios less than 2-to-1 in the direction being considered. (Commentary: Sec. A.4.2.1. Tier 2: Sec. 5.6.2)
0	\odot	\odot	\odot	considered. (commentary, sec. A.4.2.1. Her 2. sec. 5.0.2)
				Comments: Roof is plywood sheathed.
С	NC	N/A	-	SPANS: All wood diaphragms with spans greater than 24 ft (7.3 m) consist of wood structural panels or diagonal sheathing. (Commentary: Sec. A.4.2.2. Tier 2: Sec. 5.6.2)
\bigcirc		\odot	igodol	
				Comments: Plywood sheathing diaphragm is used.

UC Campi	us: Sa	nta Cruz	Date:		06/28/2019	
Building CAA	N: 7784	Auxiliary CAAN:	By Firm:	Rutherford + Cheken		kene
Building Nam	ne: Elena Baskin V	isual Arts Building H	Initials:	JY	Checked:	WAL/BL
Building Addres	SS: 427 Baskin Arts Service	e Road, Santa Cruz, CA 95064	Page:		of	
ASCE 41-17 Collapse Prevention Structural Checklist For Building Type W2 C NC N/A U DIAGONALLY SHEATHED AND UNBLOCKED DIAPHRAGMS: All diagonally sheathed or unblocked wood structure panel diaphragms have horizontal spans less than 40 ft (12.2 m) and have aspect ratios less than or equal to 4-to-4 (Commentary: Sec. A.4.2.3. Tier 2: Sec. 5.6.2) Comments: Plywood sheathing at the roof is blocked. Plywood sheathing at the main level floor is unblocked, but spans are less than 40 feet and the aspect ratios are less than 4:1						
C NC N/A U	OTHER DIAPHRAGMS: The dia bracing. (Commentary: Sec. A.4 Comments: Plywood shea	,	em other than wo	od, metal d	eck, concrete, or	horizontal

UC Campus:	Santa C	Cruz	Date:	Date: 06/28/2019			
Building CAAN:	7784	Auxiliary CAAN:	By Firm:	Rutherford + Chekene			
Building Name:	Elena Baskin Visual	Initials:	JY	Checked:	WAL/BL		
Building Address:	427 Baskin Arts Service Roa	Page:		of			

ASCE 41-17

Collapse Prevention Structural Checklist For Building Type S2-S2A

LOW SEISMICITY

SEISMIC-FORCE-RESISTING SYSTEM

			Description
NC	N/A	-	REDUNDANCY: The number of lines of braced frames in each principal direction is greater than or equal to 2. (Commentary: Sec. A.3.3.1.1. Tier 2: Sec. 5.5.1.1) Comments: In the E-W direction, two lines of steel truss braced frames and a line of wood shear wall are provided.
	N/A	-	COLUMN AXIAL STRESS CHECK: The axial stress caused by gravity loads in columns subjected to overturning forces is less than 0.10 <i>F_y</i> . Alternatively, the axial stress caused by overturning forces alone, calculated using the Quick Check procedure of Section 4.4.3.6, is less than 0.30 <i>F_y</i> . (Commentary: Sec. A.3.1.3.2. Tier 2: Sec. 5.5.2.1.3) Comments: Axial stress in the truss posts due to gravity force is 0.6 ksi per Tier 1 quick check and is less than the 5 ksi limitation. Axial stress due to overturning is 1.1 ksi and is also less than the 0.3 x 46 ksi =13.8 ksi limitation.
	N/A	-	BRACE AXIAL STRESS CHECK: The axial stress in the diagonals, calculated using the Quick Check procedure of Section 4.4.3.4, is less than 0.50 <i>F_y</i> . (Commentary: Sec. A.3.3.1.2. Tier 2: Sec. 5.5.4.1) Comments: Maximum axial stress in the diagonals of the steel trusses are estimated to be 3.1 ksi which is less than the 0.5 x 46 = 23 ksi limitation.

CONNECTIONS

				Description
C		N/A	-	TRANSFER TO STEEL FRAMES: Diaphragms are connected for transfer of seismic forces to the steel frames. (Commentary: Sec. A.5.2.2. Tier 2: Sec. 5.7.2) Comments: Shear stresses in the diaphragms are transferred to the truss chords by continuous wood blocking bolted to steel welded studs that connect to the truss elements.
C	NC	N/A	-	STEEL COLUMNS: The columns in seismic-force-resisting frames are anchored to the building foundation. (Commentary: Sec. A.5.3.1. Tier 2: Sec. 5.7.3.1) Comments: Steel post on the northeast corner is bolted to the double top plates of the wood cripple wall below, and there is no substantial out-of-plane connection between the post and the foundation to prevent the column from sliding off.

	U	IC Ca	ampu	S: Santa Cr	Santa Cruz				06/28/2019		
	Buil	ding	CAA	N: 7784	Auxiliary CAAN:		By Firm:	Ruth	Rutherford + Chekene		
	Buil	lding	Nam	e: Elena Baskin Visual A	Arts Building	н	Initials:	JY	Checked:	WAL/BL	
B	Buildir	ng Ao	ddres	S: 427 Baskin Arts Service Road	l, Santa Cruz,	CA 95064	Page:		of		
	ASCE 41-17 Collapse Prevention Structural Checklist For Building Type S2-S2A										
MC TO	MODERATE SEISMICITY (COMPLETE THE FOLLOWING ITEMS IN ADDITION TO THE ITEMS FOR LOW SEISMICITY)										
SE	SMI	IC-F	OR	CE-RESISTING SYSTEM							
						Descriptio	n				
		N/A	-	REDUNDANCY: The number of brac 5.5.1.1)	ed bays in ea	ch line is grea	ater than 2. (C	commentary:	Sec. A.3.3.1.1.	Tier 2: Sec.	
0	0	D	0	Comments: In the E-W direction, t	two lines of s	teel truss frar	nes and a line	e of wood sl	near wall are pro	ovided.	
C O			U	CONNECTION STRENGTH: All the br A.3.3.1.5. Tier 2: Sec. 5.5.4.4)				-			
				Comments: The maximum welde chord is less than the ¼" weld prov		ed at the con	nection betw	een the pos	st and the lowe	r horizontal	
	NC	N/A		COMPACT MEMBERS: All brace elen (Commentary: Sec. A.3.3.1.7. Tier 2: §		npact section	requirements i	n accordanc	e with AISC 360,	Table B4.1.	
				Comments: Maximum b/t ratio is 1 manual.	4 which is les	ss than 33 limi	itation per Tab	ble B4.1a in t	the AISC steel c	onstruction	
C O		N/A	U	K-BRACING: The bracing system does Comments: No K-bracing is used		-braced bays.	(Commentary	: Sec. A.3.3.	2.1. Tier 2: Sec.	5.5.4.6)	

HIGH SEISMICITY (COMPLETE THE FOLLOWING ITEMS IN ADDITION TO THE ITEMS FOR LOW AND MODERATE SEISMICITY)

SEISMIC-FORCE-RESISTING SYSTEM

				Description
С	NC	N/A	U	COLUMN SPLICES: All column splice details located in braced frames develop 50% of the tensile strength of the column.
				(Commentary: Sec. A.3.3.1.3. Tier 2: Sec. 5.5.4.2)
\odot		\odot	O	
				Comments: No column splices are shown in the drawings,

UC Camp	us:	Santa Cr	uz		Date:		06/28/2019		
Building CA	AN:	7784 Auxiliary CAAN:		By Firm:	Ruth	erford + Che	kene		
Building Nar	me:	Elena Baskin Visual A	Arts Building	н	Initials:	JY	Checked:	WAL/BL	
Building Addre	ess:	427 Baskin Arts Service Road	427 Baskin Arts Service Road, Santa Cruz, CA 95064				of		
Collapse	ASCE 41-17 Collapse Prevention Structural Checklist For Building Type S2-S2A								
C NC N/A U	(Commonton) Soc A 3 3 1 4 Tior 2: Soc 5 5 4 3								
	A.3	CONNECTION STRENGTH: All the brace connections develop the yield capacity of the diagonals. (Commentary: S A.3.3.1.5. Tier 2: Sec. 5.5.4.4) Comments: Complete penetration welds at the tube-to-tube connections are shown in Detail 3/S1.						entary: Sec.	
C NC N/A U	mo (29 =11 The	COMPACT MEMBERS: All brace elements meet section requirements in accordance with AISC 341, Table D1.1, for moderately ductile members. (Commentary: Sec. A.3.3.1.7. Tier 2: Sec.5.5.4) Comments: The <i>b/t</i> ratio for moderately ductile HSS sections in AISC 341-16, Table D1.1 is $0.76(E/R_yF_y)^{1/2} = 0.76(2900)/1.4x46)^{1/2} = 16.1$. The truss columns are TS7x5x1/4 (<i>b/t</i> =18.5), TS5x5x1/2 (<i>b/t</i> =7.75), and TS5x5x3/8 (<i>b/t</i> =11.3). The truss verticals are TS5x5x3/16 (<i>b/t</i> =25.7). The truss diagonals and verticals are TS5x5x3/16 (<i>b/t</i> =25.7). The truss top and bottom chords are TS5x5x1/4 (<i>b/t</i> =18.5). Thus, several members do not meet the moderately ductile requirement.					$(F_y)^{1/2} = 0.76$ 5x5x3/8 (b/t 6 (b/t = 25.7).		
C NC N/A U	sim	CHEVRON BRACING: Beams in chevron, or V-braced, bays are capable of resisting the vertical load resulting from the simultaneous yielding and buckling of the brace pairs. (Commentary: Sec. A.3.3.2.3. Tier 2: Sec. 5.5.4.6) Comments: No traditional chevron braces or "V"-braces are used.							
C NC N/A U	(Co	CONCENTRICALLY BRACED FRAME JOINTS: All the diagonal braces frame into the beam–column joints concentrical (Commentary: Sec. A.3.3.2.4. Tier 2: Sec. 5.5.4.8) Comments: No traditional concentric braced frames are used, but the truss members connections are concentric							
DIAPHRAGM	DIAPHRAGMS (STIFF OR FLEXIBLE)								
				Descriptio	n				
C NC N/A U	frai	DPENINGS AT FRAMES: Diaphragm openings immediately adjacent to the braced frames extend less than 25% of frame length. (Commentary: Sec. A.4.1.5. Tier 2: Sec. 5.6.1.3) Comments: There are no openings in the floor adjacent to the frames.				a 25% of the			
FLEXIBLE DIA	APH	IRAGMS							
	Description								

UC (Campu	IS: Santa Cr	Santa Cruz		Date:	06/28/2019		
Building	g CAA	N: 7784	7784 Auxiliary CAAN:		By Firm:	Rutherford + Chekene		kene
Buildin	g Nam	Elena Baskin Visual A	Arts Building	н	Initials:	JY	Checked:	WAL/BL
Building A	Addres	S: 427 Baskin Arts Service Road	, Santa Cruz,	CA 95064	Page:		of	
		A	SCE 4	1-17				
Colla	pse	Prevention Structur	al Che	cklist F	or Build	ding T	ype S2-S	2A
C NC N/	A U	CROSS TIES: There are continuous cr	oss ties betwe	en diaphragm	chords. (Comn	nentary: Sec	. A.4.1.2. Tier 2:	Sec. 5.6.1.2)
		Comments: For the N-S direction roof panel. For the N-S direction at						
		For the E-W direction at the roof, th	ere are no de	fined cross ti	es within eac	h sawtooth	roof panel. The	ere is metal
		"X" bridging at third points. For the	E-W directio	n at the mail	level, glulam l	beams help	serve as crossi	ies.
				<u> </u>			<u> </u>	
	A U	STRAIGHT SHEATHING: All straight-sheathed diaphragms have aspect ratios less than 2-to-1 in the direction b considered. (Commentary: Sec. A.4.2.1. Tier 2: Sec. 5.6.2)				ection being		
		Comments: Plywood sheathing is	used.					
	ΑU	SPANS: All wood diaphragms with spa		n 24 ft (7.3 m)	consist of woo	d structural	panels or diagona	al sheathing.
000		Commentary: Sec. A.4.2.2. Tier 2: Sec. 5.6.2)						
		Comments: Plywood sheathing is	Comments: Plywood sheathing is used.					
C NC N/	AU	DIAGONALLY SHEATHED AND UNBL	OCKED DIAF	HRAGMS: All	diagonally she	eathed or unb	blocked wood stru	uctural panel
000		diaphragms have horizontal spans les Sec. A.4.2.3. Tier 2: Sec. 5.6.2)	s than 40 ft (1	2.2 m) and as	spect ratios les	ss than or e	qual to 4-to-1. (C	commentary:
		,						
		Comments: Plywood sheathing is used, and it is blocked.						
	ΑU	OTHER DIAPHRAGMS: Diaphragms			other than w	ood, metal o	deck, concrete, o	or horizontal
000		Bracing. (Commentary, Sec. A.4.7.1. 1	racing. (Commentary: Sec. A.4.7.1. Tier 2: Sec. 5.6.5)					
		Comments: Plywood sheathing is	used.					



APPENDIX C

UCOP Seismic Safety Policy Falling Hazards Assessment Summary

UC Campus:	Santa Cruz			Date:		06/28/2019		
Building CAAN:	7784 Auxiliary CAAN:			By Firm:	Ruth	erford + Che	kene	
Building Name:	Elena Baskin Visual Arts Building H			Initials:	JY	Checked:	WAL/BL	
Building Address:	427 Baskin Arts Service Road, Santa Cruz, CA 95064			Page:	1	of	1	
	UCOP SEISMIC SAFETY POLICY Falling Hazard Assessment Summary							

	Description
P N/A □ ⊠	Heavy ceilings, features or ornamentation above large lecture halls, auditoriums, lobbies, or other areas where large numbers of people congregate (50 ppl or more)
	Comments: There are no heavy ceilings, features or ornamentation above the studios.
P N/A □ ⊠	Heavy masonry or stone veneer above exit ways or public access areas
	Comments: There is no heavy masonry or stone veneer at Building H.
P N/A □ ⊠	Unbraced masonry parapets, cornices, or other ornamentation above exit ways or public access areas
	Comments: There are no unreinforced masonry parapets, cornices or ornamentation at Building H.
P N/A □ ⊠	Unrestrained hazardous material storage
	Comments: No hazardous material storage was observed.
P N/A □ ⊠	Masonry chimneys
	Comments: There are no masonry chimneys.
P N/A □ ⊠	Unrestrained natural gas-fueled equipment such as water heaters, boilers, emergency generators, etc.
	Comments: Unknown.

Falling Hazards Risk: Low



APPENDIX D

Quick Check Calculations

Unit Weights:

	Selsmic Weight	Dead Load		
Floor Level	Weight [psf]		Observations	
Cementitous Topping	1.0	1.0		
Plywood Floor Sheathing	2.4	2.4	3/4" plywood	
Floor Framing	7.0	7.0	2x12 @ 16" o.c.	
Gulam Beam	1.1	11	5 1/8 x 10 1/2 x143.5' long tota	
MEP	3.0	3.0	Assumed (the lower level not entered)	
ceiling	2.0	2.0	typ. gypboard ceiling panels	
misc+lighting	3.0	3.0	Assumption (the lower level not entered)	
posts+partition+shear walls	18.4	37	wood&steel posts, int. partition, ext.wall	
Total	37.8	56.2		

Contraction of the second s	Seismic Weight	Dead Load	
Roof Level	Weight [psf]		Observations
roofing	5	5	Metal roof with insulation and 5/8° gyp
Plywood Roof Sheatning	2.3	21	5/8" plywodd
Roof Framing	7.0	7.0	2x12 @ 16" o.c.
MEP	3.0	3.0	
ceiling	2.0	2.0	typ. gypboard ceiling panels
misc+lighting	3.0	3.0	
posts+partition+shear walls	21.5	0.0	wood&steel posts, truss chords, int. partition, ext.wall
Total	44	22	

Story	W (psf)
Roof	38
1st floor	44
TOTAL	81

			Floor Trib			
wood posts in	6x6 (plf)	triba(ft)	per post (#)	# of post	total weight	weight/floor (psf)
Basement	7.35	5	36.76	12	441.15	0.25
exterior wall	2x6 @16" o.c. w/gyp. (psf)	trib area (ft^2)	plf	length	total weight	weight/floor (psf)
	12	1186			14232	8.00
interior partition walls	2x6 @16" o.c. w/ 3.5" fiberglass insulation (psf)	trib (ft)	plf	length	total weight	weight/floor (psf)
	8.85	9.5	84.075	209.5	17614	9.90
steel post of	6x4x1/2+5x5x1/2 (plf)	trib length (ft)	5x5s(plf)	trib length (ft)	total weight	weight/floor (psf)
truss	56.8	9	21	18	889.2	0.50
					total weight	weight/floor (psf)
					32734.9	18.4

			Roof Trib			
exterior wall	2x6 @16" o.c. w/gyp. (psf)	trib area (ft^2)	glazing (psf)	trib area (ft^2)	total weight	weight/roof (psf)
	12	1773	10	550	26776	15.04
steel post of	6x4x1/2+5x5x1/2 (plf)	trib length (ft)	5x5s(plf)	trib length (ft)	total weight	weight/floor (psf)
truss	56.8	34	21	68	3359.2	1.89
steel chords &	5x5 (plf)	trib length (ft)			total weight	weight/floor (psf)
diagonals of	20	406			8120	4.56
					total weight	weight/floor (psf)
					38255.2	21.5

Story Weights


Level	Area (ft ²)	Unit Weight (psf)	Seismic Weight (kips)
2nd floor	1780	38	67
1st floor	1780	44	78
TOTAL			145

Period

C,	0.02
h _{n (} ft)	25.25
β	0.75

BSE-2E Response Spectrum


Latitude, Longitude: 36.995080, -122.061000



Туре	Description	Value
Hazard Level		BSE-2E
SS	spectral response (0.2 s)	1.281
S ₁	spectral response (1.0 s)	0.485
S _{XS}	site-modified spectral response (0.2 s)	1.281
S _{X1}	site-modified spectral response (1.0 s)	0.881
fa	site amplification factor (0.2 s)	1
f _v	site amplification factor (1.0 s)	1.815

Story Shears

UCSC Building Seismic Ratings EBASK BLDG H, CAAN #7784



1.1 for wood shear wall; 1.2 steel frame. Use 1.2 to be conservative.

V [kips]

k=

Floor Levels	h, [ft]	h, [ft]	W _i [kips]	w,*h,*	coeff	F _x [kips]	V _j [kips]
2nd floor (roof)	15.25	25.25	67	1701	0.69	153	153
1st floor	10.00	10.00	78	776	0.31	70	223
Σ	1		145	2477	1.1	223	1.1

Notes:

¹ Modification Factor, C, per ASCE 41-17, Table 4-7,

223

1.00

Average Stress:

E-W direction (Longitudinal)	Steel truss frame @ Grid B	he has a second second second			
Mature	3.5	b/t=25.7 (T\$5x5x3/16) > 90*)	(Fye)^1/2 = 11.9 per 4.4.3.4	and Table 4-9 (which	has Ms
N _m	4	b/t=25.7 (T\$\$x5x3/16) > 190	"(Fye)*1/2 = 25.1 per 4.4.3.	4 and Table 4-9 (whic	h has M
Ś	80				
L.	14.8				
Ate	3.28				
E-W direction (Longitudinal)	Steel truss column @ Grid B	Steel truss column @ Grid A			
Multane	2.5		15		
L	40.5	- 16	5.0		
n.	.1.0		1.0		
h.,	17.5	- 17			
Aur	15,76	.9.	24		
· · · · · · · · · · · · · · · · · · ·	Wood shear wall				
E-W direction (Longitudinal)	Wood shear wall	CP of wood shear wall			
Master	43	CP of wood snear wall			
Level	Force (kips)		Tier 1 Shear Stress Limit ²	Units	Result
	Force (kips) 77	1/***	The second second second second	Units Isi	Result
Level Main (steel truss col OT@truss B) ¹ Main (steel truss col OT@truss A) ¹	121-20		Limit ²	1	0.00
Main (steel truss col OT@truss B) ¹	η	0.6	Umit ² 13.8 13.8	iai	OKI
Main (steel trus col OT@truss B) ¹	η	0.6	Umit ² 13.8	iai	OKI
Main (steel truss col OT@truss 8) ¹ Main (steel truss col OT@truss A) ¹	77 38	06 1.1	Limit ² 13.8 13.8 Tior 1 Shear Stress	lesi iesi	OKI OKI

Level	Force (kips)	length of wall (ft)	Avg. Shear stress (plf)	Tier 1 Shear Stress Limit	Result	
Main (Wood SW@Grid C)	38	40.5	210.4	1000	OK	
Basement (Wood SW)	223	81	613	1000	ORI	

88

A-S direction (Transverse)	Shear Walls					
M	4	4.5 CP of wood shear wall				
Level	Force (kips)	length of wall (ft)	Avg. Shear stress (plf)	Tier 1 Shear Stress Limit		
Main (Wood SW)	153	80.0	426.1	1000		

223

Notes:

Basement (Wood SW)

1. Check of steel truss columns at ends in overturning, using Equation 4-11 from Section 4.4.1.6

2. Tier 1 stress limits for axial overturning on columns is 0.3 × Fy per the 52 checklist.

Check of steel truss diagonals, using Equation 4.9 from Section 4.4.3.4.
 Tier 1 stress limits for diagonal bracing is 0.5 x Fy per the 52 checklist.

Result

OK! OK!

1000

564.0